

Item No.	GENERAL NAME OF THE ITEM	UNIT OF MEASURE	AT	ESTIMATED UNIT APPROVED BUDGET OF THE CONTRACT	ESTIMATED TOTAL APPROVED BUDGET OF THE CONTRACT	OFFERED SPECIFICATION Supplier must state how the detailed technical specifications of their offer agree with each of the individual parameters of each requirement.	OFFERED UNIT PRICE	TOTAL QUOTED PRICE	EVALUATION (Leave space blank for Evaluator's entry)
	26 05 33.13 Conduit for Electrical Systems				-				
	Supply and installation of Intermediate Metallic Conduit (IMC) including tagging, paintings, fittings, hangers, supports etc. all in accordance with drawing and specification.				-				
	20mm diameter IMC Pipe	l.m.	3.00		-				
	Supply and installation of Polyvinyl Chloride Conduit (PVC) including tagging, paintings, fittings, hangers, supports and consumables all in accordance with drawing and specification.				-				
	20 mm dia. PVC Pipe	lm	159.00		-				
	Supply and installation of Flexible Metallic Conduit (FMC) including tagging, paintings, fittings, hangers, supports and consumables all in accordance with drawing and specification.				-				
	15 mm dia. FMC	lm	7.00		-				
	26 05 33.16 Boxes for Electrical Systems				-				
	Supply and installation of boxes and pull boxes including hangers and supports.				-				
	Metal Junction Box	pcs	4.00		-				
	Metal Utility Box	pcs	2.00		-				
	Metal Square Box	pcs	2.00		-				
	26 08 00 Commissioning of Electrical Systems				-				
	Supply of labor, consumables and necessary testing equipment needed to complete the above work in accordance with the testing procedure required by the designer, owner and the project manager.	lot	1.00		-				
	26 24 00 Switchboards and Panelboards				-				
	26 24 16 Panelboards				-				
	Supply and installation of panel boards complete with nameplates, grounding, termination materials, busbars, extension busbars, breakers, supports including all necessary accessories all in accordance with the drawing and specification.				-				
	Panel: LP-A	assy	1.00		-				
	Main: LUGS ONLY In NEMA-3r Enclosure				-				
	Branches: 4 - 20AT/100AF, 2P, 10 KAIC, MCCB				-				

Item No.	GENERAL NAME OF THE ITEM	REQUIRED SPECIFICATIONS	UNIT OF MEASURE	QTY	UNIT APPROVED BUDGET OF THE CONTRACT	ESTIMATED TOTAL APPROVED BUDGET OF THE CONTRACT	OFFERED SPECIFICATION Suppliers must state how the detailed technical specification of the contract applies to each of the individual parameters of each requirement	QUOTED UNIT PRICE	TOTAL QUOTED PRICE	EVALUATION (Leave blank for Bids / Evaluators only)
	26 27 26 Wiring Devices					-				
	Supply and installation of wiring devices including necessary supports and accessories all in accordance with drawings and specification.					-				
	SWITCH					-				
	2-gang switch	sets		1.00		-				
	C.O					-				
	2-gang GFCI	sets		1.00		-				
	26 50 00 Lighting					-				
	26 51 00 Interior Lighting					-				
	26 51 19 LED Interior Lighting					-				
	Supply and installation lighting fixtures including all necessary supports, fittings consumables and other materials required to complete the system					-				
	200 mm. dia. Recessed Downlight in Aluminum Die-cast Casing with Diffuser	ea		2.00		-				
	LED Striplights with driver	lm		3.00		-				
	Wall lamp	lm		1.00		-				
						-				
	DIVISION 28 - ELECTRONIC LIFE SAFETY AND SECURITY					-				
	28 00 00 Electronic Safety and Security					-				
	28 30 00 Electronic Detection and Alarm					-				
	28 31 00 Fire Detection and Alarm System					-				
	Supply and installation of equipment and devices including necessary supports and accessories all in accordance with drawings and specification.					-				
	Smoke detector battery operated	ea		1.00		-				
	Supply of labor, consumables and necessary testing equipment needed to complete the above work in accordance with the testing procedure required by the Designer, Owner and the Project Manager. Testing and Commissioning	l.s.		1.00		-				
						-				

Item No.	GENERAL NAME OF THE ITEM	REQUIRED SPECIFICATIONS	UNIT OF MEASURE	QTY	ESTIMATED UNIT APPROVED BUDGET OF THE CONTRACT	ESTIMATED TOTAL APPROVED BUDGET OF THE CONTRACT	OFFERED SPECIFICATION Suppliers must read and understand technical specifications of their offer and all of the individual parameters of each requirement	QUOTED UNIT PRICE	TOTAL QUOTED PRICE	EVALUATION (Leave blank or submit for final evaluation only)
	DIVISION 32 - EXTERIOR IMPROVEMENTS					-				
	32 10 00 Bases, Ballasts, and Paving					-				
	Civil Works including concreting works, earthworks, base, subbase, formworks, sidewalks, curb & gutter, rebar works, surface preparation, joint sealant, joint filler, clearing, tools and consumables, and all necessary items to complete the works					-				
	Excavation Works for Pathwalk and Restroom	cum	31.58			-				
	100mm Gravel Bedding	cum	3.95			-				
						-				
	SLCC: GENERAL BUILDING CONSTRUCTION WITH Structural, Architectural, Plumbing, Electrical & Auxiliary and Site Development Works									
	Key Personnel									
	1. Licensed Civil Engineer 2. Registered Electrical Engineer 3. Licensed Master Plumber 4. Construction Safety and Health Officer (SO2) Relevant Experience: 3 years in General Building									
	Equipment									
	1 - Metal Scaffolding 1 - Power Generating Set 1 - Concrete Mixer (1 bagger) 1 - Welding Machine 1 lot - Various hand and power tools					-				
	Completion: 28 calendar days									